

Survey for the Oregon State Board of Forestry

Restoration of the monument for the 1/4 corner to Sections 31 & 32, Township 2 North, Range 5 West, W.M., Tillamook & Washington Counties, Oregon.

The point for the corner determined by the remains of the original bearing trees:

The stump hole of a fallen cedar now 20 inches in diameter, with the face burnt and cut out with part of the scribe marks "//" plainly visible, bears South 26° West, a distance of 9.9 feet (15 lks)  
The original field notes call this bearing South 26° East.

The stump hole of a fallen cedar now 20 inches in diameter, with face plain but burnt and decayed with part of the scribe marks "//" plainly visible, bears North 26° East, 9.9 feet (15 lks)  
The original field notes call this bearing North 26° West.

At the point for the corner set a 1 1/2 inch iron pipe 3 feet long, filled with charcoal, with an Oregon State Board of Forestry bronze cap stamped 1/4 S 31 S 32 1950, 199

from which:

A cedar snag 18 inches in diameter bears South 12° West, a distance of 19.8 feet. Scrib'd 1/4 S 31 199

A cedar snag 24 inches in diameter bears North 66° East, a distance of 77.4 feet. Scrib'd 1/4 S 32 199

A metal location poster on a cedar snag 18 inches in diameter bears South 65° West a distance of 47.5 feet.

Placed a mound of stones 3 feet base, 1 1/2 feet high around corner.

South of the 1/4 corner, a distance of 81 feet, a stream 1 foot wide flows SW

South of the 1/4 corner, a distance of 171 feet, placed a metal location poster on a stump on the South side of a road running SE & NW.

April 26, 1950

Present:

Lyle E. Beyers  
Glen French  
Robert Cameron

Lyle E. Beyers  
Forest Engineer

